No.	Items of work	Unit	Rate	Quantity	Cost
	V. Constructing a Returning Weir 50 feet long at R. L. 62·00.		Rs. a. p.		Rs.
1	Earthwork excavation and filling in	C.yd.	0 3 0	54	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	228	
3	Rough stone work in surki mortar	C. ft.	0 4 0	351	
4	Burnt stone 6" thick and dressed	S.ft.	0 5 0	108	
5	Pointing with cement mortar	Sqr.	4 0 0	4·74	
6	Rough stone work new	C.yd.	1 8 0	26	

P. RAJAGOPALAN,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 9th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 10th September 1936, for restoring Hatridurga Bettahally Minor Tank, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 193 .

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Hatridurga Bettahally Minor Tank, Kunigal Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Hatridurga Bettahally Minor Tank Register No. 96—118 of Kunigal Taluk.

No.	Items of work	Unit.	Rate	Quantity
			Rs. a. p.	
	BUND TO R. L. 57.00.			
1	Clearing Jungle	Grades	5 0 0	18
2	Earthwork to bund including watering and tamping	C.yds.	0 4 0	8,259
3	Cutting longitudinal trenches	C.yds.	0 3 0	1,056
4	Turfing	S.yds.	0 0 6	5,878

No.	Items of work	Unit	Rate	Quantity
5	Old stone work resetting	C.yds.	0 12 0	510
6	New stone work with jelly packing ..	C.yds.	1 8 0	2,004
7	Do with available stone from blasting	C.yds.	0 12 0	121
8	Gravel backing behind new stone revetment at breach only	C.yds.	0 6 0	468
9	Providing and fixing chiselling figures and painting Register No. stone	Each	5 0 0	1
10	Do Bench Mark stones ..	Each	3 0 0	2
11	Do Gauge Stones	Each	12 0 0	1
12	Do Grades with Index stones ..	Each	2 8 0	18
	BREACH FROM C. S. 16 TO C. S. 19.			
1	Bailing water in breach	Lumpsum	..	50 rupees.
2	Clearing silt in breach	C.yds.	0 2 6	848
3	Earthwork excavation	C.yds.	0 3 0	200
4	Benching Rock	S.ft.	0 8 0	270
5	Core wall of brick in surki mortar	C.ft.	0 4 0	1,080
6	Earthwork mixtures of gravel and clay including watering and tamping	C.yds.	0 5 0	4,674
	REPAIRING WASTE WEIR OF LEFT EXISTING 70 FEET LONG AND RAISING THE SAME OT R. L. 52.00.			
1	Brick in surki mortar	C.ft.	0 5 0	394
2	Burnt stone slabs 6" thick	S.ft.	0 7 0	121
3	Plastering with surki mortar	Sqrs.	3 8 0	5.00
	EXTENSION OF THE EXISTING WEIR BY 220 FEET TO R. L. 52.00.			
1	Earthwork excavation	C.yds.	0 3 0	286
2	Blasting rock by Gun powder to open top gabs in obstruction in front of the apron for free flow of the weir discharge	C.yds.	1 8 0	239
3	Burnt brick in surki mortar	C.ft.	0 5 0	1,749
4	Burnt stone slabs 6" thick	S.ft.	0 7 0	286
5	Plastering with surki mortar	Sqrs.	3 8 0	9.50
6	Joggles of stone plugs	No.	0 8 0	36
7	Jelly wedging old apron	S.yds.	0 8 0	168
8	New stone apron with available blasted stones .	C.yds.	0 8 0	118

N. G. KRISHNA IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 4th August 1936.

1. Sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, Chitaldrug, up to 2 P.M., on 28th August 1936, for constructing Police Lines at Davangere.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, Chitaldrug, on payment of Rupee one for each form should be addressed to the Executive Engineer, Chitaldrug Division, Chitaldrug, and should be superscribed as "Tender for constructing Police Lines at Davangere." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 500, (Five hundred only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd Thursday of September 1936. The final acceptance of the tender will rest with the Superintending Engineer, Shimoga Circle who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.